

## Sewer Disconnect Procedures

1. Verify sewer disconnect was made within 5' of property line at easement. (all sewer disconnects must be below grade)
2. Verify water meter is capped below grade. (**Note:** No hose bibbs allowed above ground, unless water service is shown to have an active and current account.)
3. Verify Centerpoint gas risers, located near structures to be demolished, are no longer actively charged with natural gas. (**Note:** Centerpoint service risers, located away from structure to be demolished, do not pose a threat to public safety)
4. Verify electric wiring has been disconnected and secured at pole in such a manner as not to present a public safety hazard. Verify electric wiring for underground service is disconnected properly. Should you have any questions, call our office and request an inspection from the electrical inspection section.

\*All requirements listed must be met before a green tag may be issued.

\*\*The objective of these procedures is to ensure there are no potential safety hazards for the demolition team and the public.